

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 05/20/05

CORNER DESIGNATION: 4N31E03, The Center Corner of Section 18.

PREVIOUS RENEWALS/SURVEYS ETC.: None.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T4N R31E
C 1 . S18
4
2005
PLS 1106

MONUMENT SET: At position established by survey, set a 2" aluminum cap on a 5/8" x 30" rebar, with cap 20" below ground level and marked as shown in Monument Marking Detail.

New Accessories:

A 5/8" x 24" rebar with a 1 1/4" yellow plastic cap marked "OR PLS 1106, WA PLS 17372", bears North 10 1/2° East, 39.5 feet.

A 5/8" x 24" rebar with a 1 1/4" yellow plastic cap marked "OR PLS 1106, WA PLS 17372", bears North 20° East, 20.1 feet

A 5/8" x 24" rebar with a 1 1/4" yellow plastic cap marked "OR PLS 1106, WA PLS 17372", bears East, 6.7 feet. Set steel fence post by this accessory and attached "witness" sign.

A 5/8" x 24" rebar with a 1 1/4" yellow plastic cap marked "OR PLS 1106, WA PLS 17372", bears South 15 1/2° East, 27.6 feet.

Rebar accessories are set in North-South fence line. Attached bearing object sign to each rebar accessory.

LOCATION AND COMMENTS:

Corner is in a wheat field, 6.3 feet West of a North-South fence line.

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

4N31E03

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-06

RECEIVED BY

Umatilla County Surveyor

Date 6-05

Rec'd By KK

No. 05-123-B