

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 3/26/15

CORNER DESIGNATION: The North One-Quarter Corner of Section 6, Township 3 North, Range 31 East, A-3.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by D.S. Payne, under Contract No. 100, dated 8/1/1861, notes state: Set charred stake with mound trench and pits as per instrs. for 1/4 sec corner.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T4N R31E
1 S31
4 S6
T3N
2015
PLS 54657

MONUMENT SET:

Held intersection of centerline of Simpson Road North-South with a field berm East and fence line West as best remaining evidence of the original corner location and set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe, with top 8" below road surface, stamped as shown in "Monument Marking Detail".

From which:

A 5/8" x 24" rebar with a 1 1/4" blue plastic cap stamped "Wells Surveying PLS 54657", bears North 25° East, 49.7 feet.

A blue deep-1 magnet, 20" below ground level, bears South 40° West, 45.5 feet.

A 3/4" brass washer stamped "PLS 1106", 2.5 feet above ground level, in a wood meter UECA pole, bears North 75° West, 21.4 feet.

A 5/8" x 24" rebar with a 1 1/4" blue plastic cap stamped "Wells Surveying PLS 54657", bears North 05° West, 62.9 feet.

Nailed witness post sign and bearing object sign to meter pole. Buried bearing object tag with magnet. Wired bearing object tags to rebar.

LOCATION AND COMMENTS: At the intersection of the centerline of Simpson Road with a field berm East and fence line West.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 773197.38

E = 8588775.82

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East
Witnesses: Jason Wells, PLS
Dean Roy

Surveyor's Seal

/3N31A3



RENEWS: 6-30-16

15-052-C