

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 4/10/15

CORNER DESIGNATION: The Northwest Corner of Section 5, Township 3 North, Range 31 East, A-5.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by D.S. Payne, under Contract No. 100, dated 8/1/1861, notes state: Set charred stake with mound trench and pits as per instructions for corner to secs 5, 6, 31 & 32.

MONUMENT AND ACCESSORIES FOUND: None

MONUMENT MARKING DETAIL:

T4N R31E
S31|S32
S6|S5
T3N
2015
PLS 54657

MONUMENT SET:

Re-established corner by single proportion measure on parallel of latitude between the North one-quarter corners of Sections 5 and 6, using GLO record. At the corner point, set a 2 3/8" brass cap on 1 1/4 by 30" galvanized iron pipe with top 20" below ground line, stamped as shown in "Monument Marking Detail".

From which:

- A silver deep-1 magnet, buried 20" in the ground, bears North 45° East, 34.8 feet.
- A pink deep-1 magnet, buried 20" in the ground, bears South 49° East, 35.1 feet.
- A blue deep-1 magnet, buried 20" in the ground, bears South 51° West, 31.9 feet.
- An orange deep-1 magnet, buried 20" in the ground, bears North 49° West, 42.7 feet.
- Buried bearing object tags with magnets.
- Set steel fence post with witness post 24 feet North 02° West of monument, in CRP field.

LOCATION AND COMMENTS: Corner located 12 feet +/- South of dim field line East-West, in farmed field.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 773209.50
E = 8591419.99

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East
Witnesses: Jason Wells, PLS
Dean Roy

Surveyor's Seal

/3N31A5



RENEWS: 6-30-16

15-052-C