

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 8/15/96

CORNER DESIGNATION: C-21. West 1/4 corner Section 1, T4N., R32E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Corner originally established by Wm. H. Odell & Wm. S. Lewis under Contract No. 110, dated February 1865.

Surveyor General records state:
Set 1/4 Sec. post; drove charred stake, dug pits and raised mound as per instructions.

MONUMENT AND ACCESSORIES FOUND: None. Found road intersection with roads north-south and east-west.

MONUMENT MARKING DETAIL:

T4N 1/4 R32E

S2 | S1

1996

ORLS 1106

MONUMENT SET: At position of intersection of visual centerlines of County Road No. 983 and County Road No. 800, set a 2 1/2 in. brass cap on a 1 1/4 in. x 30 in. galvanized iron pipe, 1 inch below asphalt (marked as shown in the monument detail).

New Accessories:

A 5/8" x 30" iron pin with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears North 51° East - 53.9 feet.

A 5/8" x 30" iron pin with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears South 39° East - 37.9 feet with a steel fence post alongside with a bearing object sign and survey marker sign attached.

A 5/8" x 30" iron pin with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears South 48° West - 32.2 feet.

A 5/8" x 30" iron pin with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372" bears North 62° West - 42.7 feet.

All iron pins have bearing object signs located near reference monuments.

LOCATION & COMMENTS: There have been virtually no original GLO corners recovered or remonumented in this township since the original survey in the 1860's. Road intersections and farmed field lines constitute best remaining evidence of the original corner locations. Prior to accepting the 4 way road intersection at this corner, I measured South from the intersection along County Road No. 983 and noted the following cultural features: at 2673', field line East; at 5412', field lines East and West; at 8074', field line West; at 10770', County Road East. This indicates "long" original measurement, but it is reasonably uniform.

COMPASS DECLINATION: 18° East.

Surveyor's Seal

FIRM/AGENCY: William R. Wells, PLS
P.O. Box 1696
Pendleton, Oregon 97801

Witness: William L. Hanley, PLS
Kelly Snively

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Will. R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-98

RECEIVED BY

Umatilla County Surveyor

Date 2-97

Rec'd By SK

No. 97-36-B