


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

N 9

History of original corner establishment:

The original corner position was established by Wm. H. Odell on July 2, 1866, under GLO contract No. 114, as follows:

Set post with a charred stake, dug pits and mounds.



Description of corner evidence found:

The original corner position is lost.

Description of monument and accessories I established to perpetuate the original location of this corner:

At the intersection of Sand Hollow Road and the Athena-Helix Highway I grout a 1" x 6" serrated and scored iron pipe. A 2 1/2" brass cap attached is marked as shown in the diagram above, from which.

A 5/8" x 30" rebar set 28" into the ground, with a red plastic cap stamped PLS 54871, bears N58°E, 64.5 feet.

A 5/8" x 30" rebar set 28" into the ground, with a red plastic cap stamped PLS 54871, bears S62°E, 80.0 feet.

A 5/8" x 30" rebar set 28" into the ground, with a red plastic cap stamped PLS 54871, bears S16°W, 41.7 feet.

A 5/8" x 30" rebar set 28" into the ground, with a red plastic cap stamped PLS 54871, bears N45°W, 26.7 feet.

I hereby certify the above corner point was perpetuated as hereon described on October 1, 2002. Bearings are true.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Thomas S. Frost

OREGON
JANUARY 19, 1999
THOMAS S. FROST
54871

REVENUE 1231-03

Office of _____ County of _____

State of _____
for record on the _____ day of _____

I hereby certify that the within instrument was filed in this office

(COUNTY OFFICIAL)

by _____

(DEPUTY)

01-73-B