

OREGON COUNTY REFORMATION FORM

COUNTY: Umatilla DATE: 05/14/97

CORNER DESIGNATION: T-1, The West Quarter Corner of Section 30, T4N., R35E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Corner established by Wm. H. Odell, GLO Contract No. 114, dated July 2, 1866. Notes state: Set 1/4 Sec. post cor; drove charred stake, dug pits and raised mound as per instructions. Corner re-established by Z.F. Moody, GLO Contract No. 164, dated October 4, 1871. Notes state: Set post and made mound of earth for 1/4 Sec. Cor. Corner re-established by Jas. P. Currin and Jas. E. Noland, under Special Contract dated May 4, 1887. Notes state: Deposited a charred stake, 12 ins. in the ground for 1/4 Sec. Cor., dug pits, 18 x 18 x 12 ins. N. & S. of Cor., 5 1/2 ft. dist., and raised a mound of earth, 1 1/2 ft. high, 3 1/2 ft. base over it; intersect pit, drove a stake, 2 ft. long, 2 ins. sq., 12 ins. in the ground, marked 1/4 on W. face.

A stone was found for the corner by Willard Bradley, County Surveyor, in April, 1915, during Bradley's County Survey No. 406.

MONUMENT AND ACCESSORIES FOUND: None. This corner position was re-established by calculation, with reference to County Survey No. 406, by Willard Bradley, dated April 1915, after recovering the South 1/16 corner and Southeast corners of Section 31 as indicated on Bradley's Survey Plat.

MONUMENT MARKING DETAIL:

T4N  
R34E R35E  
1  
4  
S25 | S30  
1997  
PLS 1106

MONUMENT SET:

Set a 2 1/2" brass cap on a 1" galvanized iron pipe 6" below surface of paved road, cap marked as shown in Monument Marking Detail.

Accessories:

A brass washer stamped "PLS 1106" nailed to Pacific Power and Light Pole #300501, bears N 72° E, 25.3 feet, with witness and bearing object signs attached.

A railroad spike stamped "PLS 1106" bears S 02° E, 42.4 feet.

A railroad spike stamped "PLS 1106" bears S 27° W, 46.5 feet.

A railroad spike stamped "PLS 1106" bears N 62° W, 20.3 feet.

Steel fence post 13.6 feet East of brass cap with witness sign attached.

LOCATION & COMMENTS: Corner located on Pambrun Road and City of Athena Well Access Road intersection, 2.5 feet West of East edge of Pambrun Road. A field line extends East from corner.

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Kelly Snively  
Jason Wells

OREGON STATE PLANE NORTH CO-ORDINATE  
FOR CORNER, NAD 83(91), INT. FEET:

N: 783089.75

E: 8712827.82

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Willi R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*Renews 6-30-98*

*97-141-C*