

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 03/02/01

CORNER DESIGNATION: V-11, North 1/4 Corner of Section 33, T4N., R34E., W.M..

PREVIOUS RENEWALS/SURVEYS ETC.: Corner was originally established by William H. Odell under Contract No. 114, dated July 2, 1866. Original notes state: Set post cor. for 1/4 Sec.; drove charred stake, dug pits and raised mound as per instructions.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T4N R34E  
1 S28  
4 S33  
2001  
PLS 1106

MONUMENT SET:

At position determined by survey, set a 2 1/2 inch brass cap on 1 1/4 inch by 30 inch galvanized iron pipe with cap buried 18 inches below ground, marked as shown in "Monument Marking Detail".

New Accessories:

A silver Deep-1 Magnet buried 18 inches in the ground bears N 52° E, 40.0 feet.

A purple Deep-1 Magnet buried 18 inches in the ground bears S 42° E, 48.4 feet.

A blue Deep-1 Magnet buried 18 inches in the ground bears S 43° W, 47.7 feet.

An orange Deep-1 Magnet buried 18 inches in the ground bears N 59° W, 36.2 feet.

New accessories have bearing object signs buried underground beside magnets.

LOCATION AND COMMENTS:

Corner is approximately 40 feet North of a field line which runs North along the East line of the NW1/4 of Section 33 and then runs West in farmed field.

FIRM: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Witnesses: Jason Wells, LSIT  
Kevin Snively

4N34V11

Surveyor's Seal

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*renews 6-30-02*

RECEIVED BY

Umatilla County Surveyor

Date 4-01

Rec'd by KK

No. 01-52-C