

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 10/27/03

CORNER DESIGNATION: P-21, The West 1/4 Corner of Section 24, T4N, R36E, W.M..

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by Wm. Odell, under Contract No. 114, dated July 2, 1866. Notes state: Set post Cor. for 1/4 Sec. From which:
A Larch, 18 ins. diam brs. S 05°W., 18 lks.
A Larch, 20 ins. diam. brs. N10°E., 15 lks.

MONUMENT AND ACCESSORIES FOUND:
Found western larch bearing tree, now a 24" cut stump, 4' above ground, with fence wire attached and extending South, East and West from the stump. Found scribing "B" visible after opening blaze. Nothing remains of the other bearing tree.

MONUMENT MARKING DETAIL:
T4N R36E
1/4
S23|S24
2003
PLS 1106

MONUMENT SET:
At a point North 05° East., 11.9' (18 lks) from face of blaze on western larch bearing tree stump, set a 2 1/2" brass cap on a 1 1/4" x 30" galvanized iron pipe 26" in the ground, surrounded with a mound of earth. Cap is marked as shown in "Monument Marking Detail".

New Accessories:
A 18" fir bears N 04°W., 29.3' scribed "1/4 S23 BT".
A 12" fir bears S 44°E., 2.7' scribed "1/4 S24 BT".
A 16" fir bears S 37°W., 19.8' scribed "1/4 S23 BT".
A 12" fir bears N 50°W., 27.5' scribed "1/4 S23 BT".

New bearing trees have a brass washer stamped "PLS 1106" nail to face of blaze, and a "bearing object" sign attached. Measurements to new bearing trees are to the center of tree.

Set steel fence post South of Corner monument and attached "witness" sign.

LOCATION AND COMMENTS: Corner falls on steep East slope about 70 feet South of Dry Creek.

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT
Mark Hammersla

4N36P21

REGISTERED
PROFESSIONAL
LAND SURVEYOR
William R. Wells
OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106
renews 6-30-04

03-317-B