

CEI ED RECORD OF LAND CORNER MONUMENTATION


T 4N, R 36E . , W.M.

Corner Code No. X-13

Note: Monument marked as shown below

History of original corner establishment:

This corner was originally established by William Odell, U.S. Deputy Surveyor, under Contract No. 117, dated July 2, 1866. The original notes state that at the corner a wood post was set for the corner with charred stake and stone mound.



Corner No.
Compass Declination: 19.0°

Description of corner evidence found:

None.

Description of monument and accessories I established to perpetuate the original location of this corner:

Reestablished corner at a point on an old north-south fence line, at a point 2.5 chains record (165'), north of Pine creek. Set a 2 1/2" brass cap on 1 1/2" by 30" galv. iron pipe, 20" in the ground to bedrock, and surrounded with a mound of earth and stone from which:

A 22" douglas fir bears N49°W 31.0' scribed 1/4 S33 BT.
A 6' by 6' by 7' out of ground rock in place, bears N70°E 7.0' marked "X B0" on west face.

Bearing tree has a bearing object sign attached. Set steel fence post South of corner and attached witness corner sign.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

7-27-88

Office of Survey County of Umatilla
State of Ore I hereby certify that the within instrument was filed in this office
for record on the 28th day of July, 1988
David H. Lumb by William R. Wells
(COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY

Umatilla County Surveyor

Date 7-88 GPO-788-278

Rec'd By AT

No. 88-42-C