

**OREGON CORNER RESTORATION FORM**

**Section:** 13 & 14

**Township:** 4 North

**Range:** 37 East, W.M.

**County:** Umatilla

**Date:** 08/14/2000

**Corner Designation:** K.5-21, South-North 1/64 corner common to Sections 13 & 14.

**Previous Renewals/Surveys, etc.:** None

**Monument(s) & Accessories Found (Condition & Source):** None

**Monument Detail:** T4N R37E

E 1/64

SE 1/4 NE 1/4

+

S14

2000

LS 2820

**Monument Set (Procedures & Description):** At the position determined by survey, set a 1"x 30" galvanized iron pipe 28" in the ground with a 2 1/2" brass cap attached.

**New Accessories:** Set 6' steel fence post 3' North of the corner. A 10" Douglas fir bears N24°E 34.9 feet marked 1/64 S13 BT. A 5/8"x30" rebar (RM) with a yellow plastic cap stamped "TOMKINS SURVEYING" bears N90°E 10.7 feet. A 5/8"x30" rebar (RM) with a yellow plastic cap stamped "TOMKINS SURVEYING" bears S0°E 11.4 feet. A 30" white fir bears N32°W 51.9 feet marked 1/64 S14 BT.

All bearing trees have a 6" wide red band painted around them and bearing object signs attached.

The reference monuments (RM) have a steel fence post with a bearing object sign attached set alongside.

**Location & Comments:** This corner is located on a steep Northeasterly facing slope near the bottom of Tamarack Basin 800'± South of the South Fork of the Walla Walla River.

**Compass Declination:**

19° East

**Firm/Agency:** Tomkins Land Surveying, Inc.

20 E. Poplar, Suite 204

Walla Walla WA 99362

**Party Chief:** Josh Martin

**Notes:** Josh Martin

**Witness:** Ryan Laughery

**Surveyor's Seal**

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Greg E. Flowers*

OREGON  
JUNE 30, 1997  
GREG E. FLOWERS  
02820LS

RENEWS 12/31/01

*12/15/00*

**RECEIVED BY**

Umatilla County Surveyor

Date 12-00

Rec'd by SM

No. 00-25-8-C