

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 10/30/03

CORNER DESIGNATION: P-25, The East 1/4 Corner of Section 24, T4N, R36E, W.M..

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by Wm. Odell, under Contract No. 114, dated July 2, 1866. Notes state: Set post Cor. for 1/4 Sec. From which:
A Pine, 31 ins. diam brs. West., 127 lks.
A Pine, 14 ins. diam. brs. N40°E., 145 lks.

MONUMENT AND ACCESSORIES FOUND:
None. I reestablished the corner at the mean intersection of old fence line running East-West and North.

MONUMENT MARKING DETAIL:

T4N
R36E|R37E
1/4
S24|S19
2003
PLS 1106

MONUMENT SET:

At mean intersection of old fences extending East-West and North, set a 2 1/2" brass cap on a 1 1/4" x 30" galvanized iron pipe 26" in the ground, surrounded with a mound of earth. Cap is marked as shown in "Monument Marking Detail".

New Accessories:

A 60 penny spike driven in the center of a pitched 30" sawn pine stump bears N 49°E., 178.2'. Measured to 60 penny spike.
A 7" Ponderosa pine bears S 69° E., 109.4' scribed "1/4 S19 BT".
A 8" Ponderosa pine bears S 27°W., 89.1' scribed "1/4 S24 BT".
"XBO" chiseled in a 44" by 20" by 12 above ground rock bears S 85° W., 21.5'. Measured to the "X".

New bearing trees have a brass washer stamped "PLS 1106" nail to face of blaze, and a "bearing object" sign attached. Attached "bearing object" sign to the sawn stump accessory. Measurements to new bearing trees are to the center of tree.

Set steel fence post East of Corner monument and attached "witness" sign.

LOCATION AND COMMENTS: Corner is located in a meadow.

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT
Mark Hammersla

14N36P25

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-04

03-317-B