

OREGON CORNER RESTORATION FORM

Section 24,25 Township 4N Range 37E W.M.
County Umatilla Date 8/1/93
CORNER DESIGNATION: R-23

Previous Renewals/Surveys, etc. The original survey was made by George S. Pershin, under contract No. 332, dated July 29th, 1879. He set a fir post on s side of spur in mound of stone for 1/4 Sec. Cor. from which:
A fir, 14 ins. diam. brs. N.8°E., 168 lks. dist.
No tree on S. side. Campbell found the corner in 1901, Hambleton found the BT in 1977 (map No. N-65).

Monument(s) & Accessories Found: (Condition and Source) Found a rotted stump with visible BT scribed on it that had been disturbed by logging operations, was able to find original stump location.
Found no evidence of original stone mound.

Monument Detail:

T4N R37E
1 S24
4 S25
1993 OR 1106

Monument Set (Procedures and Description): Bed rock is 6-8" below the surface. I chiseled a hole in the rock 2" wide x 6" long, 4" deep, and set a railroad spike, head down in the crack and secured it with concrete patch, a 1" aluminum cap marked as indicated in the monument detail is firmly attached, and built a stone mound around it.

New Accessories:

A rock out cropping X BO with a P.K. nail in it 2' N. of the end and 4' above ground brs. S.57°E., 47.7 ft.
A 5/8" x 30" rebar with a plastic cap stamped WE WELLS PLS 1107, set 12" in the ground with a mound of stone to the top brs. S.45°W., 23.6 ft.
A large rock outcropping X BO with a P.K. nail in it 6' above ground and 10' S. of the crest of the spur brs. N.57°W., 127.1 ft.
A 5/8" x 30" rebar with a plastic cap stamped WR WELLS PLS 1106, set 8" in the ground with a mound of stones to the top brs. N.4°E., 37.1 ft.
A steel fence post in a rock mound with a Land Survey Marker sign attached brs. N. 3.2 ft.

Location & Comments: The corner is located on a steep open hillside about 50' S. of the top of the spur and 300" E. of where a logging road crosses the spur.

Compass Declination: 18° E
Firm/agency: Tomkins-Wells Joint Venture
Land Surveying
P.O. Box 1696
Pendleton, Oregon 97801

Party Chief: Greg Flowers
Notes: Greg Flowers
Witness: Todd Rosenbalm

Surveyor's Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

expires 12-31-94

93-64-C