

RTIFIED RECORD OF LAND CORNER MONUMENTATION

T 4N, R 37E., W.M.

Corner Code No. R-3


Note: Monument marked as shown below

History of original corner establishment:

This corner was originally established by William Odell, U.S. Deputy Surveyor, under Contract No. 114, dated July 2, 1992. The original notes state:

Set post cor. for 1/4 Sec. from which:

A pine, 18 ins. diam. brs. S 80°W, 310 lks.  
A pine, 15 ins. diam. brs. N 30°E, 75 lks.



Corner No.  
Compass Declination: 18.0°

Description of corner evidence found:

Re-established by single proportion measure between the N.E. and N.W. corners of section 30. Corner falls about 34' South of East-West fence and 30' East of North-South fence. Corner falls just South of an old road bed.

Note: There is a burnt stump located N 11 3/4°E, 63' from the corner. Beside the stump is a slab of wood with older and more recent axe marks, and a possible scribe mark. The stump and slab are both burnt. The slab of wood does not appear to have been attached to the stump, and there are no matching marks or faces between the stump and the face. The burnt stump does not appear old enough to be the original Northeast bearing tree. I do not believe there is sufficient evidence to utilize the stump as the original Northeast bearing tree.

Description of monument and accessories established to perpetuate the original location of this corner:

Set a 2 1/2" brass cap on a 1 1/4" by 30" galv. iron pipe 15" in ground to bedrock and surrounded with a mound of earth and stone. Cap marked as shown.

Set a steel fence post East of corner and attached a Witness corner sign.

New Bearing Trees:

A 8" ponderosa pine bears N 75°W - 141.2', scribed 1/4S19BT.  
A 10" ponderosa pine bears N 51°W - 112.1', scribed 1/4S19BT.  
A 21" ponderosa pine bears N 27 1/2°W - 93.3', scribed 1/4S19BT.  
A 12" ponderosa pine bears N 84 1/2°E - 83.3', scribed 1/4S19BT.

There are no trees close to the corner on the South side.

Note: There is a Oregon Forestry location poster on a 22" ponderosa pine just Northwest of the fence corner to the Northwest.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

Office of..... County of.....  
State of....., I hereby certify that the within instrument was filed in this office  
for record on the..... day of....., 19.....  
..... by .....  
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

**RECEIVED BY**  
Umatilla County Surveyor  
Date 7-92  
Rec'd By JK  
No. 92-79-B

☆ GPO-788-276