

OREGON CORNER RESTORATION FORM

Section 25,26 Township 4N Range 37E W.M.
County Umatilla Date 8/1/93
CORNER DESIGNATION: T-21

Previous Renewals/Surveys, etc. The original survey was made by George S. Pershin, under contract No. 332, dated July 29th, 1879. He set a fir post on steep E. hillside for 1/4 Sec. Cor from which
A fir, 5 ins. diam. brs. N.18°E., 90 lks. dist.
A fir, 12 ins. diam. brs. N.58°W., 125 lks. dist.
On his map dated 2/15/77 James Hambleton indicates that he found the original GLO corner (file No. N-65 Umatilla County records).
Monument(s) & Accessories Found: (Condition and Source) Found a mound of stones with nail and old survey lath in it on a steep E. slope, from which:
A 24" fir snag stump with BT scribed on it brs. N.58°W., 75.1 ft. (82.5 ft. if measured along the slope).
A 20" fir snag stump with BT scribed on it brs. N.27°E., 55.5 ft. (59.4 ft. if measured along the slope).

Monument Detail:

T4N $\frac{1}{4}$ R37E
S26 | S25
1993
1106

Monument Set (Procedures and Description):

Set a 5/8" x 30" rebar with a 1" aluminum cap stamped as indicated in the monument detail, 28" in the ground with a stone mound around it, at the location of the stone mound and nail.

New Accessories:

A 21" fir with a scar on the S. side brs. N.57°W., 57.3 ft. marked T4N R37E S26 BT
A 14" fir brs. N.31°E., 48.5 ft. marked T4N R37E S25 BT.
A rock outcropping 6' x 10' With a P.K. nail 1.5' down from the top and 2' west of the point brs. S.42°E., 79.6 ft.
A 5/8" x 30" rebar with a 1' aluminum cap stamped BO set 27" in the ground brs. S.10°W., 32.0 ft.
A steel fence post with Land Survey Monument sign attached brs. N. 3.0 ft.
Location & Comments: The corner is on a steep open E. slope, I set the rebar instead of the pipe monument because the hillside is unstable and the rebar is more likely to stay put.

Compass Declination: 18° E

Surveyor's Seal

Firm/agency: Tomkins-Wells Joint Venture
Land Surveying
P.O. Box 1696
Pendleton, Oregon 97801

Party Chief: Greg Flowers
Notes: Greg Flowers
Witness: Todd Rosenbalm

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

EXPIRES 12-31-94

93-64c