

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 4N, R 37E., W.M.

Corner Code No. V-15  
 Note: Monument marked as shown below

History of original corner establishment:


This corner was originally established by George S. Pershin, U.S. Deputy Surveyor, under Contract No. 332, dated July 27, 1879.

The original notes state:

Set Fir post in small open glade for 1/4 Sec. Cor. on S.W. hillside.

A fir 13 in. di. brs N 34°E 81 lks. dist.  
 A fir 24 in. di. brs S 46°W 111 lks. dist.

In 1978, Douglas M. Ferguson recovered evidence of the original bearing trees and set a small stone mound at the corner point by utilizing original record bearing tree calls. See corner certificate No. Q-731.



Corner No.  
 Compass Declination: 18.0°

Description of corner evidence found:

Found 6" nail set in a small stone mound from which:

A 28" sawn douglas fir stump bears N 34°E 53.5' to blaze face and 54.0' to centerline, with chopped open blaze and fragmentary scribes visible. (original bearing tree).  
 A 48" uprooted white fir bears S 46°W 73.3' plus or minus to root hole, with chopped open face on down side of tree. (original bearing tree).

Description of monument and accessories I established to perpetuate the original location of this corner:

At the position of the found nail in the small stone mound I set a 2 1/2" brass cap on a 1 1/4" by 30" galvanized iron pipe, 20" in the ground and surrounded with a mound of earth and stone. Set steel fence post near corner with witness corner sign attached.

Marked four new bearing trees:

A 12" western larch bears N 27 1/2°E 49.4' scribed 1/4 S27 BT.  
 A 10" douglas fir bears N 48 1/2°W 92.0' scribed 1/4 S27 BT.  
 A 8" douglas fir bears S 34°W 33.6' scribed 1/4 S34 BT.  
 A 12" western larch bears S 82 1/2°E 79.7' scribed 1/4 S34 BT.

Attached bearing object signs to all bearing trees.

There is an East-West fenceline about 15' South of corner and a North-South fenceline about 60' to the West.

REGISTERED  
 PROFESSIONAL  
 LAND SURVEYOR

*William R. Wells*

OREGON  
 JULY 22, 1977  
 WILLIAM R. WELLS  
 1106

Office of..... County of.....  
 State of....., I hereby certify that the within instrument was filed in this office  
 for record on the..... day of....., 19.....

..... by .....  
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY  
 Umatilla County Surveyor  
 Date 9-91  
 Rec'd By [Signature]  
 No. 91-25-C