

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 4N, R 37E., W.M.

Corner Code No. V-3

Note: Monument marked as shown below


History of original corner establishment:

This corner was originally established by W. H. Odell, U.S. Deputy Surveyor, under Contract No. 114, dated July 2, 1866.

The original notes state set post corner for 1/4 section from which:

A fir, 10 in dia. bears N 82° E 22 lks.  
A fir, 12 in dia. bears S 32° W 15 lks.

This corner was re-established by single proportion measurement by Guy W. Streater, P.E., in 1974 as shown on Survey No. I-153-C.



Corner No.  
Compass Declination: 18.0°

Description of corner evidence found:

1/2" by 24" iron pin, as noted on Survey I-153-C.

Description of monument and accessories I established to perpetuate the original location of this corner:

At the position of the found 1/2" by 24" iron pin, the location confirmed by survey between the Northwest and Northeast corners of Section 31, I set a 2 1/2" brass cap on a 1 1/4" by 30" galvanized iron pipe, 38" in the ground. The top of the monument is buried 8" below ground to avoid damage by road grading and snow plowing. Buried the 1/2" iron pin below the new monument on the North side.

The corner monument is referenced as follows:

- A 10" western larch bears N 42 1/2° E 74.8', scribed 1/4 S30 BT.
- A 14" douglas fir bears N 25° W 57.9', scribed 1/4 S30 BT.
- A 4" western larch bears S 77 1/2° E 29.1', scribed "X" at breast height and "BT" at base of tree.
- A brass washer stamped PLS 1106, nailed to the North side of UECA pole No. 305007, 6" above ground bears S 58 1/2° E 22.8'.

Placed bearing object signs on the bearing trees.

Set steel fence post 3.0' East of corner and attached witness corner sign.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

Office of..... County of.....  
 State of....., I hereby certify that the within instrument was filed in this office  
 for record on the..... day of....., 19.....  
 ..... by .....  
 (COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY

Umatilla County Surveyor

☆ OPO-788-276

Date 9-9/

Rec'd By JK

No. 91-75-C