

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 4N, R 37E., W.M.

Corner Code No. X-5

Note: Monument marked as shown below

History of original corner establishment:


This corner was originally established by W.H. Odell, U.S. Deputy surveyor, under contract No. 114, dated July 2, 1866.

The original notes state:

Set post corner for 1/4 section, from which:

- A larch 20 in. dia. bears N 37° W, 52 lks dist.
- A larch 6 in. dia. bears S 80° E, 10 lks dist.

This corner was reportedly re-established under Survey No. I-153-C, in 1974.



Corner No.
Compass Declination: 18.0°

Description of corner evidence found:

Found a 2 1/2" O.D. pipe with 2 bearing trees from survey No. I-153-C.

This monument was rejected because it bears S 21° 17' E 6.52 feet from position as determined by this survey.

Description of monument and accessories I established to perpetuate the original location of this corner:

The position for this corner was determined by relating resurvey measurements made on Survey No. S-154-B, to a solar basis as observed on Survey No. P-113-B. A solar observation was made at the 2" iron pipe set under Survey No. I-153-C and the true corner position re-established relative to the 2" iron pipe. See accompanying map of survey for further explanation.

Set a 2 1/2" brass cap on a 1 1/4" by 30" galvanized iron pipe 24" in ground and surrounded with a mound of earth and broken concrete.

Used old bearing trees and marked 2 new ones:

- A 12" douglas fir bears S 77 1/2° E, 8.1', with partly healed blaze. (Survey I-153-C).
- A 11" western larch bears S 57° W, 8.9', with partly healed blaze. (Survey I-153-C).
- A 8" western larch bears S 04° E, 21.6', scribed 1/4 S32 BT.
- A 9" Englemann spruce bears S 10° W, 8.7', scribed 1/4 S31 BT.

Placed bearing object signs on all bearing trees.

Set steel fence post North of corner and attached a witness corner sign.

REGISTERED PROFESSIONAL LAND SURVEYOR
<i>William R. Wells</i>
OREGON JULY 22, 1977 WILLIAM R. WELLS 1106

Office of..... County of.....
 State of....., I hereby certify that the within instrument was filed in this office
 for record on the..... day of....., 19.....
 by
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY

☆ GPO-798-276

Umatilla County Surveyor
 Date 9-91
 Rec'd By RF
 No. 91-25-C