


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

The original survey was made by George E. Pershin under contract No. 304 dated Sept. 19, 1878. He set a fir post in a small open glade on level for 1/4 sec. cor. He set the following bearing trees:
A pine 11" dia. bears N 05 E, 104 lks. dist.
A fir 8" dia. bears S 14 E, 135 lks. dist.



Description of corner evidence found:

I found a small glade as described in the GIO notes and in the glade I found a small mound of stone of which I tied to my co-ordinate system. Though there was no record of a mound of stone at this location, after a thorough search and extensive work through the area I found the mound to be harmonious with the surrounding evidence and found corners, thus I determined the mound of stone to be a perpetuation of the original 1/4 corner.

Description of monument and accessories I established to perpetuate the original location of this corner

None



Office of..... County of.....
 State of....., I hereby certify that the within instrument was filed in this office
 for record on the day of

..... by

(COUNTY OFFICIAL) (DEPUTY)