

2-21

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:


Corner established by George S. Pershin under G.L.O. contract number 304 dated Sept., 19, 1878.

Surveyor General's records state:

Set a spruce post on nearly level for corner to sections 1-2-35 & 36 from which:

A fir 10" diam. bears S 48° E., 229 lks dist marked T 3 N R 37 E S 1 BT
A fir 48" diam. bears N 43° W., 188 lks dist marked T 4 N R 37 E S 35 BT

No other green trees near.



2-21

Description of corner evidence found:

NONE

Description of monument and accessories established to perpetuate the original location of this corner

Set a 2 1/2" brass cap on a 2" iron pipe 31" long 6" above the ground with a 6' steel fence post 3' north with sign 54-4 attached.

new bearing trees:

A fir 12" diam. bears S 21° W., 51.0 ft. dist. marked T 3 N R 37 E S 2 BT
A fir 15" diam. bears S 32° E., 105.0 ft. dist. marked T 3 N R 37 E S 1 BT
A fir 12" diam. bears N 71° W., 60.0 ft dist. marked T 4 N R 37 E S 35 BT
A fir 12" diam. bears N 51° E., 110.0 ft. dist. marked T 4 N R 37 E S 36 BT

Each BT has a sign 54-3 attached 6" below a band of red paint and has a brass washer marked RPE 2808 nailed flush with BT blaze.



Office of.....Surveyor..... County of...Umatilla.....

State of Oregon....., I hereby certify that the within instrument was filed in this office for record on the 26. day of August, 1976.....

..... by (COUNTY OFFICIAL) (DEPUTY)