

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 4N, R 37E., W.M.

Corner Code No. Z-5

Note: Monument marked as shown below

History of original corner establishment:


This corner was originally established by W.H. Odell, U.S. Deputy Surveyor, under Contract No. 114, dated July 2, 1866.

The original notes state:

Set post corner for sections 31, 32, 5, and 6, from which:

- A fir 8 in. dia. bears S 6°E, 18 links.
- A fir 6 in. dia. bears N 45°E, 11 links.
- A fir 20 in. dia. bears S 40°W, 40 links.
- A fir 7 in. dia. bears N 54°W, 32 links.

In 1974, under Survey No. I-153-C, a 1 1/2" reinforcing steel was reportedly set at the re-established corner position.



Corner No.
Compass Declination: 18.0°

Description of corner evidence found:

Found 1 1/4" axel from Survey I-153-C. Axel bears S 06° 51' E, 12.31' from corner position as determined by this survey.

The position of the axel was rejected because it is not in the proper location.

Description of monument and accessories established to perpetuate the original location of this corner:

Re-established corner position by single proportion measurement between the Southwest corner of Section 31, and the Southeast corner of Section 32, and set a 2 1/2" brass cap on a 1 1/4" by 30" galvanized iron pipe, 24" in ground and surrounded with a mound of earth.

From the new monument:

- A 18" white fir bears S 55°E, 38.2', with partly healed blaze. (Survey I-153-C).
- A 11" white fir bears S 39°W, 17.1', with partly healed blaze. (Survey I-153-C).
- A 10" Englemann spruce bears N 08°W, 30.4', scribed T4N R37E S31 BT.

Put bearing object signs on all trees and on steel fence post by axel monument.

Set a steel fence post North of corner with a witness corner sign attached.

There is a East by West fence and road 30' South of corner.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....

..... by (DEPUTY)

(COUNTY OFFICIAL)

Form R6-7100-57 (9/71)

RECEIVED BY

Umatilla County Surveyor

Date 9-91

Rec'd By KE

No. 91-25-C

★ OPO-798-276