

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 4N, R 37E., W.M.

Corner Code No. Z-9

Note: Monument marked as shown below


History of original corner establishment:

This corner was originally established by W.H. Odell, U.S. Deputy Surveyor, under Contract No. 114, dated July 2, 1866.

The original notes state:

Set post corner for sections 4, 5, 32 & 33 from which:

A fir 20 in dia bears S 97° W, 19 links.
 A fir 19 in dia bears S 40° E, 39 links.
 A fir 20 in dia bears N 40° E, 40 links.
 A fir 18 in dia bears N 3° W, 9 links.



Corner No.
Compass Declination: 18.0°

Description of corner evidence found:

Found 12 by 9 by 4" stone, marked with 6 grooves on North and South edges, and marked with an "X" on top, set just South of a 4 way fence corner, with fences going North, South, East & West.

This stone has been used as the corner on several previous surveys and is accepted as the perpetuation of the original corner monument.

Description of monument and accessories I established to perpetuate the original location of this corner:

At the position of the "X" on the marked stone, set a 2 1/2" brass cap on a 1 1/4" by 30" galvanized iron pipe, 24" in the ground and surrounded with a mound of earth. Placed marked stone in the new mound on the West side of the new monument.

Marked 4 new bearing trees:

A 9" white fir bears N 75 1/2° E 29.7' scribed T4N R37E S33 BT.
 A 8" white fir bears S 19° E 10.9' scribed T3N R37E S4 BT.
 A 12" Englemann spruce bears S 39° W 32.7' scribed T3N R37E S5 BT.
 A 6" lodgepole pine bears N 58° W 21.4' scribed T4N R37E S32 BT.

Placed bearing object signs on the new bearing trees.

Set steel fence post South of corner and attached witness corner sign.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19....

..... by
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY

☆ GPO-789-276

Umatilla County Surveyor

Date 9-91

Rec'd By KK

No. 91-25-C