


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Not previously established.



0-19

Description of corner evidence found:

N/A

Description of monument and accessories established to perpetuate the original location of this corner:

Set 3"x30" galv. iron pipe with 3" brass cap stamped as shown in the diagram, set 20" in the ground.

From which:

A pine 20 in. dia. bears S71°E, 14.2 ft. scribed C N 1/16 S 23 BT.

A pine 12" in. dia. bears S52°W, 31.2 ft. scribed C N 1/16 S 23 BT.

Set steel posts with warning and boundary signs 5 ft. East and 5 ft.

North from corner. Nailed bearing tree signs and brass washers stamped PLS 848 to each tree. Painted a red band around each tree.

I Hereby certify that the above corner monument was established on 8/12/81 as herein described.

Witnesses:

D. Mitchell Ferguson

Mike Woodward



Office of... Co. Surveyor..... County of... Umatilla.....
 State of... Oregon..... I hereby certify that the within instrument was filed in this office
 for record on the... 2nd day of... January....., 19... 82
 David Krumbein by Billy Shatto
 (COUNTY OFFICIAL) (DEPUTY)

82-01-B

T-2