

USDA-FOREST SERVICE

Index File No. P-19

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or Survey No. \_\_\_\_\_ Cor. No. \_\_\_\_\_


T 4 S R. 30E

R.D. Ukiah County Umatilla

Merid. Willamette

N.F. Umatilla State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

Not previously established.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

N/A

PHOTO IDENTIFICATION DATA

Photo No. \_\_\_\_\_  
 Filed At. \_\_\_\_\_  
 Object Ident. \_\_\_\_\_  
 Ident. By \_\_\_\_\_  
 Signature \_\_\_\_\_

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner is on top of ridge, approximately 20 ft. North of ridge road.

PLANE COORDINATE POSITION DATA

State \_\_\_\_\_ Zone \_\_\_\_\_  
 X \_\_\_\_\_  
 Y \_\_\_\_\_  
 Estab. By \_\_\_\_\_  
 Agency \_\_\_\_\_

Signature \_\_\_\_\_ Title \_\_\_\_\_ Division \_\_\_\_\_ Headquarters \_\_\_\_\_ Date \_\_\_\_\_  
 Surveyor Mt. Vernon, OR 7/28/81

7100-52-(3/68)

**CORNER RECORD (PERPETUATION)**

**MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT**

Set 3"x30" galv. iron pipe with 3" brass cap, stamped as shown in the diagram, set 14" in the ground and raised a mound of stone around the pipe.

**ACCESSORIES : DESCRIBE NEW BT's WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE**

From which: A pine 24 in. dia. bears N27°30'E, 20.2 ft. scribed C1/4 S23 BT. No other trees available.

Set wood post with location poster and boundary sign 5 ft. South. Set steel post with warning sign and boundary sign 5 ft. East. Nailed bearing tree tag and brass washer stamped PLS 848 to tree. Painted red band around tree.

Work Done By D.M. Ferguson Title Surveyor Date 7/28/81 State Registration No. or Agency OR PLS 848

Certified ~~or~~ ~~Reviewed~~ Prepared? Yes  No  Filed At: Umatilla Co. Surveyor Date 10/81

**PROFESSIONAL  
LAND SURVEYOR**

REMARKS

Witnesses to above corner:

D. Mitchell Ferguson  
Mike Woodward

OREGON  
JULY 12, 1968  
DOUGLAS M. FERGUSON  
848