


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Not previously established.



Q-19

Description of corner evidence found:

N/A

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 3"x30" galv. iron pipe with 3" brass cap stamped as shown on the diagram. Set 12" in the ground and raised a mound of stone around the pipe. From which:

A pine 14" dia. bears S82°E, 34.3 ft. scribed C S 1/16 S 23 BT.
 A pine 10" dia. bears S50°W, 91.4 ft. scribed C S 1/16 S 23 BT.
 Set steel posts with warning and boundary signs 10 ft. East and 10 ft. North from corner.
 Nailed bearing tree tags, brass washers stamped PLS 848 and painted red band around each tree.

I hereby certify that the above corner monument was established on 7/27/81 as herein described.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Douglas M. Ferguson
OREGON
JULY 12, 1969
DOUGLAS M. FERGUSON
848

Witnesses: D. Mitchell Ferguson

D. Herburger

Office of Co. Surveyor County of Umatilla
 State of Oregon I hereby certify that the within instrument was filed in this office
 for record on the 17 day of January, 1982
David R. Rasmussen by Betty Shatt
 (COUNTY OFFICIAL) (DEPUTY)

82-018