

USDA-FOREST SERVICE

Index File No. Q-20

T 45 R 30E

Merid. Willamette

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

R.D. Ukiah County Umatilla

N.F. Umatilla State Oregon

Tract or Survey No. _____ Cor. No. _____

CORNER DIAGRAM

T45 R30E

SE 1/16 S 23

1981

PLS 848



DESCRIBE CORNER MONUMENT FOUND

Corner not previously set.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

N/A

PHOTO IDENTIFICATION DATA

Photo No. _____

Filed At. _____

Object Ident. _____

Ident. By _____

Signature

PLANE COORDINATE POSITION DATA

State _____ Zone _____

X _____

Y _____

Estab. By _____

Agency

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner is approx. 500 ft. South from ridge road in open ground, near the top of the ridge on a slight South slope. Go South from road at a point approx. 1000 ft. West of a "Y" in the road.

Signature

Title

Division

Headquarters

Date

7100-52-(3,68)

PLS 848

Mt. Vernon, OR

7/27/81

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set 3"x30" galv. iron pipe with 3" brass cap stamped as shown on the diagram. Set 12" in the ground and raised a mound of stone around the pipe.

From which:

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

A pine 14 in. dia. bears S63° 45' W, 196.0 ft. scribed SE 1/16 S 23 BT, No other trees available.
Set steel posts with warning and boundary signs 10 ft. South and 10 ft. West from corner. Nailed bearing tree sign and brass washer stamped PLS 848 to tree. Painted a red band around the tree.

Work Done By D.M. Ferguson Title Surveyor Date 7/27/81 State Registration No. OR PLS 848
or Agency

~~Certified Copy~~ Prepared? Yes No Filed At: Umatilla Co. Surv. Office Date 10/81

**PROFESSIONAL
LAND SURVEYOR**

REMARKS

Douglas M. Ferguson
**OREGON
JULY 12, 1988
DOUGLAS M. FERGUSON
848**