


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established in 1882 by George S. Pershin under General Land Office Contract No. 430. Surveyor General's records state: Set a stone 16 x 8 x 7 ins. and post 4 ft. long 4 ins. square in a mound of stone on S.W. slope for cor. to Sec. 23,24, 25 and 26. Stone marked with 2 notches on S. and 1 notch on E edges.



R-21

Description of corner evidence found:

No evidence found. An old fence line courses N70°E - S70°W, approx. 50 ft. North of cor. position. The original mound of stones and original stone were probably placed in the old fence line.

No bearing trees originally taken.

Since no evidence is found, corner is set by proportion.

Description of monument and accessories established to perpetuate the original location of this corner:

Set 3"x30" galv. iron pipe with 3" brass cap, stamped as shown on the diagram, set 6 in. in the ground and raised a mound of stone and earth around the pipe. (Mound is 8' x 24".)

From which:

A pine 20" dia. bears N42°W, 102.6 ft. scribed T45, R30E, S23 BT.

A pine 16" dia. bears S50°E, 63.0 ft. scribed T45, R30E, S25 BT.

A pine 10" dia. bears S29°W, 93.4 ft. scribed T45, R30E, S26 BT.

No bearing tree available in NE quadrant.

Set steel posts with warning and boundary signs 6 ft. West and 6 ft. East from corner. Nailed bearing tree signs and brass washers stamped PLS 848 on each tree.

Painted red band around each tree.

I hereby certify that the above corner monument was reestablished on 8/26/81 as herein described.

Witnesses:

D. Mitchell Ferguson

Mike Woodward



Office of... Co. Surveyor... County of... Umatilla... State of... Oregon... I hereby certify that the within instrument was filed in this office for record on the 7th day of January, 1982... David Krumholz by Betty Shatt... (COUNTY OFFICIAL) (DEPUTY)

82-01-6

T-2