


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner not previously established.



T-24

Description of corner evidence found:

N/A

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 3"x30" galv. iron pipe with 3" brass cap stamped as shown on the diagram. Pipe set 6 inches in the ground and raised a mound of stone around the pipe.

From which:

A pine 10 inches dia. bears S61°W, 118.2 ft. scribed CE 1/16 S 25 BT. No other tree available.

Set steel posts with warning and boundary signs 6 ft. North and 8 ft. East from corner.

Nailed bearing tree sign and brass washer stamped PLS 848 to tree. Painted a red band around the tree.

I hereby certify that the above corner monument was established as herein described on 7/29/81.

Witnesses:

D. Mitchell Ferguson

Mike Woodward

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Douglas M. Ferguson
OREGON
JULY 12, 1968
DOUGLAS M. FERGUSON
848

Office of... Co. Surveyor..... County of... Umatilla.....
State of... Oregon..... I hereby certify that the within instrument was filed in this office
for record on the... 1st... day of... January....., 1982
David B. Mason, Jr. by Betty Shatto
(COUNTY OFFICIAL) (DEPUTY)

82-01-C

T-2