


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner not previously established.



U-22

Description of corner evidence found:

N/A

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 3"x30" galv. iron pipe with 3" brass cap stamped as shown on the diagram. Set pipe 18 inches in ground and raised a mound of stone around the pipe.

From which:

A pine 13 inches dia. bears N52°E, 103.0 ft. scribed SW 1/16 S 25 BT,

A pine 12 inches dia. bears S79°W, 201.2 ft. scribed SW 1/16 S 25 BT.

Set steel posts with warning and boundary signs 5 ft. East and 5 ft. North from corner.

Nailed bearing tree signs and brass washers stamped PLS 848 to each tree. Painted red band around each tree.

I hereby certify that the above corner monument was established as herein described, on 7/30/81.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 12, 1968
DOUGLAS M. FERGUSON
848

Witnesses:

D. Mitchell Ferguson

Mike Woodward

Office of... Co. Surveyor..... County of... Umatilla

State of... Oregon..... I hereby certify that the within instrument was filed in this office

for record on the... 25 day of... January....., 1982

..... David Krumm..... by Betty Skitts.....
(COUNTY OFFICIAL) (DEPUTY)

82-01-C