


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner not previously established.



U-23

Description of corner evidence found:

N/A

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 3"x30" galv. iron pipe with 3" brass cap stamped as shown on the diagram Set pipe 26 inches in the ground.

From which:


A pine 12 inches dia. bears N51°W, 53.8 ft. scribed CS 1/16 S 25 BT.
 A pine 13 inches dia. bears S88°E, 7.7 ft. scribed CS 1/16 S 25 BT.
 Set steel posts with warning and boundary signs 5 ft. South and 5 ft. West from corner.
 Nailed bearing tree signs and brass washers stamped PLS 848 to each tree.
 Painted red band around each tree.

I hereby certify that the above corner monument was established as herein described, on 7/30/81.

Witnesses:

D. Mitchell Ferguson

Mike Woodward



Office of... Co. Surveyor... County of... Umatilla
 Oregon
 State of... , I hereby certify that the within instrument was filed in this office
 for record on the... day of... January... , 1982
 David Kraushaar by Betty Shatto
 (COUNTY OFFICIAL) (DEPUTY)

87-01-C