


**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

**History of original corner establishment:**

This corner was originally established by George S. Pershin under G.L.O. contract no. 430 dated March 23, 1882. He set a basalt stone 20"x12"x6" 15" in the ground marked 1/2 on the west side.

From which:  
A Pine, 30" dia., N16°E, 61 lks

No other tree was available. He raised a stone mound alongside the corner.



**Description of corner evidence found:**

Found a stone 20"x11"x6" with no marks evident and a stone mound.

From the corner:  
A pine stump, burned and rotted, approximately 3 1/2' diameter, N14°E, 42.2 ft. with no scribing remaining.

**Description of monument and accessories established to perpetuate the original location of this corner:**

In place of the stone set a 2 1/2"x30" alum. pipe with a 3" alum. cap containing a magnet and marked:

Buried the original stone alongside and built a stone mound around the monument.

From the corner:  
New BTs  
A P. Pine, 9" dia., N73 1/2°E, 45.3 ft. marked 1/2 S35 BT  
A.D. Fir, 8" dia., S55 1/2°W, 22.4 ft. marked 1/2 S34 BT

BTs have blaze and a 6" stripe painted red, a BT tag and an "Attention" sign. The new BTs have alum. "PLS 1832" washer nailed to the bottom of the blaze. There is a 6' steel fence post with an "Attention" sign within 5' of the corner.

Measured to center of BTs using steel tape and theodolite; bearings are true.  
September 18, 1984.

T4S R30E

1/2

S34 | S35  
PLS 1832  
1984

**REGISTERED  
PROFESSIONAL  
LAND SURVEYOR**

*Fayette S. Munro*

**OREGON  
JULY 13, 1979  
FAYETTE S. MUNRO  
1832**

Office of Surveyor County of Linnetilla  
State of Oregon I hereby certify that the within instrument was filed in this office  
Record on the 10 day of October, 1984  
David H. Krumbain by Fayette S. Munro  
(COUNTY OFFICIAL) (DEPUTY)

X-17