


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. E-11

History of original corner establishment:

Corner established in June, 1881, by George S. Pershin, under General Land Office contract. Surveyor General's records state:

"Set basalt stone 16x8x5 on slight S.E. slope for 1/4 Sec. Cor.  
A Pine 9 in. diam. brs. N24°W, 9 lks. dist.  
A Pine 10 in. diam. brs. S22°E, 52 lks. dist."




Description of corner evidence found:

Couldn't find any trace of the original stone or any of the bearing trees.

Description of monument and accessories established to perpetuate the original location of this corner:

Set 2 1/2"x30" galvanized pipe with brass cap marked:  
Pipe is set 24" in ground. Mound of stone to cap.

A Fir 16" in dia. bears N18°E 81.0 ft., scribed 1/4 S4 BT. A Fir 20" in dia. bears S73°W, 19.2 ft., scribed 1/4 S9 BT. Attached brass washer, stamped PLS 1051, to foot blaze of each BT. Attached 54-3 and 54-4 signs to each BT. Set painted metal fence post 5 ft. west of monument with 54-4 sign attached. Painted a 6" band around each BT and both blazes on each B.T. red.



I hereby certify the above corner monument was reestablished as herein described.

Witnesses: R. Orton  
G. Lester

December 7, 1980  
See Record Plat for S9, T4S, R32E, W.M. as filed with the Umatilla County Surveyor.

Office of County Surveyor County of Umatilla  
Oregon  
 State of Oregon, I hereby certify that the within instrument was filed in this office  
 for record on the 7 day of December, 1980  
Howard L. Perry by Betty Scott  
 (COUNTY OFFICIAL) (DEPUTY)

E-11

R-187-B