


Index
File No. G-17
T 4S R. 32E
Merid. W.M.

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or
Survey No. _____ Cor. No. 1/4
R.D. Ukiah County Umatilla
N.F. Umatilla State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

20"x15"x6" basalt stone in small mound of stone clearly marked 1/4 on west side.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

From which: A Pine 20" in dia. bears S18°E, 129 feet. Completely grown over blaze.
A Pine 41" in dia. with double top bears S22°W, 141 feet. Both blazes grown over but evident.

PHOTO IDENTIFICATION DATA

Photo No. _____
Filed At. _____
Object Ident. _____
Ident. By _____
Signature

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner is about 100' east of fire road in scrubby pine.

PLANE COORDINATE POSITION DATA

State _____ Zone _____
X _____
Y _____
Estab. By _____
Agency

Barney B. Barbour Signature Title P.L.S. Division _____ Headquarters _____ Date 10/3/77 7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

OR PLS 1051

1/4

S10 + S11

T4S R32E

1977

Set 2½" x 30" galvanized iron pipe with brass cap marked:
 Set pipe 10" to bedrock and mound of stone around.
 Placed marked stone at base of pipe.

9

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

New BTs. A pine 10" in dia. bears S75°E, 23.5 feet, scribed 1/4 S11 BT.
 A pine 12" in dia. bears N84°W, 52.0 feet, scribed 1/4 S10 BT.
 Placed 53s and 54-4s on all four BTs.
 Placed brass washer stamped PLS 1051 on foot blazes of new BTs.
 Placed 54-4 on fence post 3 feet south.
 Painted 6" red band on trees and painted both blazes red.

10

Work Done By Barry B. Barboun Title P.L.S. Date 10/3/77 State Registration No. OR PLS 1051
 or Agency

Certified Cor. Record Prepared? Yes No Filed At: _____ Date _____

11

REMARKS

Witness: D.L. Landers

12

Index File No. _____ T. _____ R. _____ M. _____ Tract or Surv. No. _____ Cor. _____

13