

Index File No. L-17

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or Survey No. _____

Cor. No. 1/4

T 4S R. 32E

R.D. Ukiah


County Umatilla

Merid. W.M.

N.F. Umatilla

State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

Found 14"x13"x8" Basalt Stone in small mound, clearly marked 1/4 on west side.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

A Pine 22" in diameter bears S66 $\frac{1}{2}$ °W 40.8 feet, scribed 1/4S BT. A Pine 28" in diameter bears N56°E 39.5 feet. Blaze grown over.

PHOTO IDENTIFICATION DATA

Photo No. _____

Filed At. _____

Object Ident. _____

Ident. By _____

Signature

PLANE COORDINATE POSITION DATA

State _____ Zone _____

X _____

Y _____

Estab. By _____

Agency

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner is on steep west slope on the west edge of small clearing.

Bobby B. Barber

Title

PLS

Division

Headquarters

Date

10/25/77

7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

T4S R32E

Set 2½" x 30" galvanized pipe with brass cap marked:

$$\begin{array}{c} \frac{1}{4} \\ | \\ S15 \text{ --- } S14 \end{array}$$

Set pipe 24" in the ground with mound of stone around. Placed corner stone at base of pipe.

OR PLS 1051
1977

9

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

New BT. A fir 18" in diameter bears N20°E, 18.0 feet, scribed 1/4 S14 BT. Placed 54-3's and 54-4's on bearing trees. Painted 6" red band and both blazes red on new B.T. Placed brass washer stamped PLS 1051 on foot blaze of new B.T. Placed 54-4 on fence post 4' east of corner.

10

Work Done By. B.B. Barbour Title P.L.S. Date 10/25/77 State Registration No. OR PLS 1051
or Agency

Certified Cor. Record Prepared? Yes No Filed At: _____ Date _____

11

REMARKS

Witness to the above corner: D.L. Landers
S. Nelson

12

Index File No.

T.

R.

M.

Tract or Surv. No.

Cor.

13