


Index
File No. M-17
T 4S R. R32E
Merid. W.M.

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

R.D. Ukiah County Umatilla
N.F. Umatilla State Oregon
Tract or Survey No. _____
Cor. No. S1/16

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

None Set.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None Set.

PHOTO IDENTIFICATION DATA

Photo No. _____
Filed At. _____
Object Ident. _____
Ident. By _____
Signature

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner falls about 400 feet west of a fire road on west slope.

PLANE COORDINATE POSITION DATA

State _____ Zone _____
X _____
Y _____
Estab. By _____
Agency

Barney B. Barbour

Title P.L.S. Division _____ Headquarters _____

Date 10/25/77 7100-52-(3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

At surveyed point: Set 2 1/2"x30" galvanized pipe with brass cap marked:
Set pipe 20" in the ground to bedrock with mound of stone around.

T4S R32E
S 1/16
S15 † S14
OR PLS 1051
1977

9

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

From which a Pine 24" in dia. bears N66°W, 36.4 feet, scribed S1/16 S15 BT. A Pine 24" in dia. bears S75°E, 29.8 feet, scribed S1/16 S14 BT. Placed 54-3 and 54-4 signs on BT's and brass washer stamped PLS 1051 on foot blazes. Painted 6" red band around BT's and painted both blazes red. Placed 54-2 and 54-9 on fence post 4' East of corner. Placed 54-2 and 54-4 on fence post 5' South of corner.

10

Work Done By B.B. Barbour Title P.L.S. Date 10/25/77 State Registration No OR PLS 1051
for Agency

Certified Cor. Record Prepared ? Yes No Filed At: Date

11

REMARKS

Witnesses: D.L. Landers
S. Nelson

12