

USDA-FOREST SERVICE

Index File No. M-21
 T 4S R. 32E
 Merid. W.M.


CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

R.D. Ukiah County Umatilla
 N.F. Umatilla State Oregon

Tract or Survey No. _____
 Cor. No. S1/16

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

None Set.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None Set.

PHOTO IDENTIFICATION DATA

Photo No. _____
 Filed At. _____
 Object Ident. _____
 Ident. By _____
Signature

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner falls about 750 feet west of a fire road in scattered timber.

PLANE COORDINATE POSITION DATA

State _____ Zone _____
 X _____
 Y _____
 Estab. By _____
Agency

Barry B. Barbour

Signature Title P.L.S. Division _____ Headquarters _____ Date 10/25/77

7100-52-(3/68)

CORNER RECORD (PERPETUATION)

GPO 902-673

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

At surveyed point: Set 2½"x30" galvanized pipe with brass cap marked:
Set pipe 22" in the ground with mound of stone around.

OR PLS 1051

S 1/16

S14 + S13

T4S R32E

1977

9

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

From which a Pine 13" in diameter bears N85°W, 31.9 feet, scribed S1/16 S14 BT. A Pine 18" in diameter bears S69°E, 37.0 feet scribed S1/16 S13 BT. Placed 54-3 and 54-4 on both BT's. Placed brass washer stamped PLS 1051 on foot blazes of BT's. Painted 6" red band around BT's and both blazes red. Placed 54-2 and 54-4 on fence post 6 feet west of corner. Placed 54-2 and 54-9 on fence post 3 feet south of corner.

10

Work Done By B.B. Barbour Title P.L.S. Date 10/25/77 State Registration No. OR PLS 1051
for Agency

Certified Cor. Record Prepared ? Yes No Filed At: _____ Date _____

11

REMARKS

**Witnesses to the above corner: D.L. Landers
S. Nelson**

12