

Index File No. M-7  
T 4S R. 32E  
Merid. W.M.


CORNER RECORD (SEARCH)

(Ref. FSM-7151.4)

R.D. Ukiah County Umatilla  
N.F. Umatilla State Oregon

Tract or Survey No. \_\_\_\_\_  
Cor. No. CS1/16

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

None Set.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None Set.

PHOTO IDENTIFICATION DATA

Photo No. \_\_\_\_\_  
Filed At. \_\_\_\_\_  
Object Ident. \_\_\_\_\_  
Ident. By \_\_\_\_\_  
*Signature*

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner falls about 5 feet south of a fence in thick timber.

PLANE COORDINATE POSITION DATA

State \_\_\_\_\_ Zone \_\_\_\_\_  
X \_\_\_\_\_  
Y \_\_\_\_\_  
Estab. By \_\_\_\_\_  
*Agency*

*Barry B. Barbour*

*Signature* Title P.L.S. Division \_\_\_\_\_ Headquarters \_\_\_\_\_ Date 11/4/77  
7100-52-(3/68)

## CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

T4S R32E

Set 2½"x30" galvanized pipe with brass cap marked:  
 Set pipe 18" in the ground to bedrock with mound of stone around to cap.

S1/16 + S17

 C  
 C  
 OR PLS 1051  
 1977 9

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

A Fir 12" in dia. bears S26°E, 10.9', scribed S1/16 S17 BT.  
 A Fir 12" in dia. bears S52°W, 16.6', scribed S1/16 S17 BT.  
 Placed 54-3, 54-4 and brass washer stamped PLS 1051 on BT blaze.  
 Painted both blazes red and red band around BTs.  
 Placed 54-2, 54-4 and 54-9 on fence posts 3' west and 3' north of corner.

10

 Work Done By. B.B. Barbour Title P.L.S. Date 11/4/77 State Registration No. OR PLS 1051  
 or Agency

Certified Cor. Record Prepared ? Yes No Filed At: Date

11

## REMARKS

 Witnesses: D.L. Landers  
 S. Nelson

12

Index File No. T. R. M. Tract or Surv. No. Cor.

13