

Index
File No. N-11

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or Survey No. _____ Cor. No. _____

T 4 S R. 32 E

R.D. Ukiah County Umatilla

Merid. Willamette

N.F. Umatilla State Oregon

CORNER DIAGRAM

T 4 S R 32 E

$\frac{1}{4}$ S 16
 S 21



1977

DESCRIBE CORNER MONUMENT FOUND

Found 2½" iron pipe with 3¼" brass cap (as shown in corner diagram) in mound of stone.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

A 38" ponderosa pine brs N52°E, 119.3' with scribing visible.
A 27" ponderosa pine brs S26¼°E, 65.4' with healed blaze.

PHOTO IDENTIFICATION DATA

Photo No. _____

Filed At. _____

Object Ident. _____

Ident. By _____

Signature

PLANE COORDINATE POSITION DATA

State _____ Zone _____

X _____

Y _____

Estab. By _____

Agency

Signature

Walter R. Wall

Title
Land Surveyor

Division

Headquarters
Pendleton, Ore.

Date
6-03-92

FS-7100-52 (3/68)

6

7

8

2

3

4

5

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set steel fence post next to corner with sign 54-9 & 54-2 attached.

Compass declination 18° East.

9

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

New bearing trees established:

A 19" ponderosa pine brs S35½°E, 32.6' scribed 1/4S21 BT

A 11" ponderosa pine brs N46°E, 79.6' scribed 1/4S16 BT.

New BT's have a brass washer stamped PLS 1106 nailed to face of blaze.

Attached sign 54-3 & 54-9, painted face of blaze & a 6" red band around each BT.

10

Work Done By. W.R. Wells Title Land Surveyor Date 6-03-92 State Registration No. ORLS 1106
or Agency

Certified Cor. Record Prepared ? Yes ~~XXX~~ Filed At: Umatilla County Surveyor Date 7-92

REMARKS

12

13

Index File No. N-11 T. 4 S R. 32 E M Tract or Surv. No. Cor. WM.