


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. Z-13

History of original corner establishment:

In 1881, under GLO Contract No. 410, George S. Pershin set stone 16x10x5, from which a 20" Pine bears N40°W, 168 lks. and a 12" Pine bears S82°E, 113 lks.




Description of corner evidence found:

Found BLM 3 1/4" brass cap on 2 1/2" iron pipe in mound of stones with 3 ft. radius at the base and 1 ft. high. Cap rises 6" above mound, stamped:

Bearing Trees Found:

- A 12.8" P. Pine bears N75°E, 31.5 Ft., scribing visible "T3S R33E S4 BT".
- A 35" D. Fir bears S85°E, 74.2 ft., some scribing visible in healing blaze.
- A 10.1" D. Fir bears S13°W, 114.7 ft., scribing visible "T4S R33E S4 BT".
- A 28.2" P. Pine bears N37°W (BLM record N40°W) 115.2 ft., scribing visible "T3S R33E S".



Description of monument and accessories I established to perpetuate the original location of this corner:

Added rocks and earth to stabilize mound.

Painted blazes and attached signs as per Standard Specifications for Cadastral Surveys, USFS Region 6, March, 1982.

Compass Declination: 19 1/2°E Witness: N. Petz

Set metal fence post 1 ft. north of corner.

From the intersection of 2110-044 & 2110, southeasterly on 2110 1/2 mi. Corner is about 450 ft. north of the road.

I hereby certify the above described corner monument and/or accessories was established as described on September 15, 1983.



Office of Surveyor County of Umatilla
 State of Oregon, I hereby certify that the within instrument was filed in this office
 for record on the 15th day of July, 1983
David Krumholz by Betty Cochran
 (COUNTY OFFICIAL) (DEPUTY)