


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. Z-17

History of original corner establishment:

In 1881, under GLO Contract No. 410, George S. Pershin set a stone 16x10x5, from which an 8" Pine bears N69°W, 68 lks.; a 10" Pine bears S51°W, 89 lks.; and a 24" Pine bears S21°E, 136 lks.



Description of corner evidence found:

No corner monument found.

Bearing tree found:

A 3 1/2" P. Pine stump 6 ft. high, bears S21°E, 89.8 ft. to face of blaze, scribing visible "4S R33E S2".

Description of monument and accessories established to perpetuate the original location of this corner:

Set 2 1/2"x30" aluminum capped aluminum pipe rising 14" in mound of stone and earth. Cap stamped:

New BT's:

- A 5" W. Larch bears N66 1/4°W, 60.6 ft., scribed "X" BT.
- An 1 1/2" P. Pine bears N47°E, 112.8 ft., scribed T3S R33E S35 BT.
- A 5" W. Larch bears S31°E, 157.9 ft., scribed "X" BT.
- A 15 1/2" W. Larch bears S57°W, 113.5 ft., scribed T4S R33E S3 BT.

T3S R33E
S34 | S35
S3 | S2
 T4S
 1984
 RLS 1848

Painted blazes and attached signs as per Standard Specifications for Cadastral Surveys, USFS Region 6, March 1982.

Compass Declination: 19 1/2°E

Witness: G. Arrand

Set metal fence post 4 ft. north of corner.

From intersection of 2110-220 & 2110-049, SW BT is visible 200 ft. NE.

I hereby certify the above described corner monument and/or accessories was established as described on May 22, 1984.



Office of Surveyor County of Umatilla
 State of Oregon I hereby certify that the within instrument was filed in this office for record on the 10th day of July, 1984
David K. Rumber by Betty Cochran
(COUNTY OFFICIAL) (DEPUTY)