

Index

File No. N-19

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or Survey No. _____

Cor. No. 1/4

T 4S R. 33E


R.D. Ukiah County Umatilla

Merid. Willamette

N.F. Umatilla State Oregon

CORNER DIAGRAM

T4S R33E



DESCRIBE CORNER MONUMENT FOUND

NONE

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

NONE

PHOTO IDENTIFICATION DATA

Photo No. _____
 Filed At. _____
 Object Ident. _____
 Ident. By _____
Signature

PLANE COORDINATE POSITION DATA

State _____ Zone _____
 X _____
 Y _____
 Estab. By _____
Agency

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

From Junction of Ukiah-Hilgard Highway and Forest Road 54 Go East 1.0 Mi., take Road to North for 0.5 Mi., to "Y", take right fork, GO 0.5 Mi., Park, walk uphill 50 feet to corner.

Signature
David H Klein

Title
PLS 933

Division _____

Headquarters _____


Date
7-1983

7100-52 (3. 68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set a 2 1/2" dia. Brass Cap on a 2 1/2" x 30" Galvanized Pipe
Set 15" in the Ground Marked!



ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

A 12" dia. Ponderosa Pine bears S 69° 45' W 37.7 Feet scribed 1/4 S 35 BT
A 14" dia. Ponderosa Pine bears N 68° 45' W 42.6 Feet scribed 1/4 S 26 BT
Blazes are Painted red and have red bands around them.
Trees have SIGNS Numbers 54-3, 54-4 and Brass Washers Stamped PL5 933
Nailed to them.

Work Done By D. Krumboltz Title Surveyor Date 7-83 State Registration No. PL5 933
or Agency

Certified Cor. Record Prepared? Yes No Filed At: Umatilla County Date 7-83

REMARKS