


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Unsurveyed - subdivided section.



No record of subsequent remonumentation found in County Records.

Description of corner evidence found:

No evidence found.

Description of monument and accessories I established to perpetuate the original location of this corner:

At the position described above, I set a 2 1/2" x 30" iron pipe with a 2 1/2" Brass Cap 24" in the ground with a brass cap marked as shown:

From which I scribed BT's:

A 36" Pond Pine bears S 47°45'E 18.30 feet scribed C 1/4 S 35  
A 9" Pond Pine bears S 50°W 25.90 feet scribed C 1/4 S 35

I nailed a brass washer marked PLS 933 to the BT blazes.


I set signs 54-3 and 54-9.

I painted a red band around the BT's and face of scribe.

I used a steel tape and a magnetic compass with 19°30' East variation and measured a horizontal distance to the center of BT's.

This corner was set March 1984

Witness: Rod PUNCHES  
Brent REYNOLDS



REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

David H. Krumben  
OREGON  
JULY 17, 1970  
DAVID H. KRUMBEN  
933

Office of.....County Surveyor..... County of.....Umatilla  
Oregon  
State of.....I hereby certify that the within instrument was filed in this office  
for record on the 26 day of November, 1984  
..... by Betty Cochran  
(COUNTY OFFICIAL) (DEPUTY)