


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. A-25

**History of original corner establishment:** Corner established in 1881 by George S. Pershin, under G.L.O. Contract No. 410. Surveyor General's notes state:

Set post 5 ins. square 5 ft. long on level on long open glade for Corner to Townships 4 & 5 South Ranges 33 & 34 East marked: T4S R34E S31 on NE side.  
 T5S R34E S6 on SE side.  
 T5S R33E S1 on SW side.  
 T4S R33E S36 on NW side.


Also marked with 6 notches on N., E., S. & W edges. Raised mound of stone 2½ ft. high and 5½ ft. base around post in lieu of pits.



**Description of corner evidence found:** At assumed corner location found mound of stone one foot high and 6 ft. wide with dirt covering most of stones. Found traces of rotted wood about 2 ft. below top of mound of stone, possible remains of original post. Found remains of old East-West fence.

**Description of monument and accessories established to perpetuate the**

**original location of this corner:** As evidence in the vicinity of corner agrees with GLO original record, in the center of stone mound where traces of rotted wood was found set 2½"x30" galvanized pipe with brass cap stamped:




Set pipe 26" in ground with mound of stone to cap. From which:

A P. Pine 24" in dia. bears S39°W, 402.7 ft., scribed T5S R33 E S1 BT. No trees within distance for Northwest BT. Due to wetness of glade it was felt impractical to set bearing object. Attached 54-3 and 54-4 signs to BT. Attached brass washer stamped LS1294 to foot blaze of BT. Painted blazes and 6" band around BT red. Attached 54-4 sign to metal post 6 ft. south of corner.

1980  
OR PLS 1294

I hereby certify that the above corner monument was reestablished as herein described on May 28, 1980.

Witnesses: R. Orton  
 G. Lester  
 L. Huntsman



Office of..... County Surveyor..... County of..... Umatilla  
 Oregon  
 State of..... I hereby certify that the within instrument was filed in this office  
 for record on the..... day of..... December..... 19..80  
 ..... David..... by..... Betty Shatto  
 (COUNTY OFFICIAL) (DEPUTY)