

OREGON CORNER RESTORATION FORM

SECTION: 19 TOWNSHIP: 5N RANGE: 29E N-1

COUNTY: UMATILLA DATE: 12/05

CORNER DESIGNATION

NW Section 19

- CONDITION REPORT ONLY
- NOT FOUND
- RENEWED
- UNRECORDED
- SURVEYED IN
- REFERENCED OUT

PREVIOUS RENEWALS/SURVEYS ETC.

Originally surveyed by Davenport under Contract # 101 in 1861. He set post and made mound. In 1988 county contract in T5N R28E; Edwards set 1"x30 iron pipe with 2 3/8" brass cap.

MONUMENTS AND ACCESSORIES FOUND: CONDITION AND SOURCE

Found 2 3/8" brass cap 4" above the surface stamped as detail.

MONUMENT DETAIL

T5N
R28E R29E
S13|S18
S24|S19
1988
L.S. 951

OREGON STATE PLANE COORDINATES, NORTH ZONE, NAD 83(91) INT. FEET:

819576.79
8521601.61

MONUMENT SET (PROCEDURES AND DESCRIPTION)

NEW ACCESSORIES FROM WHICH

- A 5/8" x 30" Iron Rebar with plastic cap #951 bears N 59° 05' 11" E 59.69'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears N 66° 51' 07" W 45.61'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 47° 43' 31" W 34.05'
- A 5/8" x 30" Iron Rebar with plastic cap #951 bears S 12° 13' 06" E 52.00'

LOCATION AND COMMENTS

From intersection of Craig Rd. with Hwy # 730, go West on 730 one mile. Corner lies approximately 500' South of Hwy.

SURVEYOR'S SEAL

FIRM: EDWARDS SURVEYING LLC
PO BOX 763 - HERMISTON OR 97838

PARTY CHIEF: R. SMITH
WITNESS: J. JOSEPH

REGISTERED
PROFESSIONAL
LAND SURVEYOR

G. Dennis Edwards

OREGON
JULY 16, 1971
G. DENNIS EDWARDS
9 5 1

RENEWS 12/31/05