

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: February 1998

CORNER DESIGNATION: N-9, Northeast corner of Section 20, T5N., R28E., W.M.

PREVIOUS RENEWALS/SURVEYS ETC.: Original GLO Survey by Timothy W. Davenport, under Contract No. 101, dated August 5, 1861. Notes state: Cor. to Secs. 16, 17, 20 & 21. A point in bed of River, from which, 20 lks. W. and 20 lks. N., upon an island, 25 lks. broad and 4.00 chs. long, I established a witness Cor. of stone and post, from which an alder, 4 ins. diam., brs. S.W. 22 lks. dist. The Umatilla River, here, is about 5.00 chs. broad, the water being spread over nearly the whole bed and runs N20°W. Re-established by Frank A. Tuers, under Special Instructions, Group No. 864, dated April 11, 1975. Notes state: Set a brass tablet, 3 1/4 ins. diam., 3 1/2 in. stem, in drill hole in solid rock, with brass cap mkd: T5N R28E, S17 | S16

S20 | S21, 1975. Maintained by G. Dennis Edwards, Umatilla County Survey Record #91-01-B, dated January 1991. Record states: Fnd. 2 1/2" B.C. imbedded in rock river bed stamped as shown above (Tuers). Found 2 1/2" iron pipe W.C. with 2 1/2" B.C. N 79°31' W, 211.79 feet. New Accessories: The face of a 7" diameter bridge column Bears N58°E 33.9 feet. The face of a 7" diameter bridge column Bears S21°W 92.3 feet. The face of a 7" diameter bridge column Bears N29°W 133.7 feet.

MONUMENT AND ACCESSORIES FOUND:

Found a 3 1/4" brass cap reference monument, on 2 1/2" iron pipe, 4" above ground, marked as shown in "Monument Marking Detail".

Found a project boundry post and sign bearing S 85° W, 3.55 feet.

MONUMENT MARKING DETAIL:

US DEPT OF THE INTERIOR

T5N R28E

S17 RM

211.73 FT

TO COR

1975

CADASTRAL SURVEY

BUR. OF LAND MANAGEMENT

MONUMENT SET:

New Accessories referencing reference monument:

A 5/8" x 30" iron rod with yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", bears N 66° E, 11.47 feet

The center of a 7.0 foot diameter bridge column bears South, 133.21 feet.

A brass washer stamped "PLS 1106", 1.0 foot above ground in a railroad tie bears N 03° W, 2.40 feet.

5/8" iron rod has steel fence post nearby with witness sign attached.

Reference monument has a steel fence post nearby with witness sign attached.

LOCATION AND COMMENTS: At intersection of River Road and I-82, corner lies under Northbound bridge. 150 feet West of River Road and in river bed. Could not access true corner monument at time of survey.

COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: Jason Wells
Benjamin Weinke

Oregon State Plane Coordinates, North Zone, NAD 83(91), Int. Feet:

For Reference Monument:

North: 819393.15

East: 8500146.41

For Calculated Corner Point:

North: 819357.62

East: 8500355.12

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Will R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

98-101-C

Renews 6-30-98