

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 03/24/05

CORNER DESIGNATION: 5N35, L-09, The East Quarter Corner of Section 17.

**PREVIOUS RENEWALS/SURVEYS ETC.:**

Corner originally established by Odell & Lewis, under GLO Contract No. 110, dated February 7, 1865. Notes state: Set 1/4 Sec. post; drove charred stake; dug pits & raised mound, as per instructions.

This corner was searched but not recovered by J.C. Arnold, in 1887, under Record of Private Surveys, Survey No. 27.

MONUMENT AND ACCESSORIES FOUND: None.

**MONUMENT MARKING DETAIL:**

T5N R35E  
1/4  
S17|S16  
2005  
PLS 1106

**MONUMENT SET:**

Corner area has been extensively farmed. I re-established this corner position perpendicular to the midpoint of a line between the Northeast and Southeast corners of Section 17, holding the existing North-South fence line for departure. At the re-established corner position, set a 2 1/2" brass cap on a 2 1/2" x 30" galvanized iron pipe, 32" in the ground.

**New accessories:**

A 5/8" x 24" rebar with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372", set in fence line, bears North, 21.1 feet.

A 5/8" x 24" rebar with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372", set in fence line, bears North, 43.1 feet.

A 5/8" x 24" rebar with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372", set in fence line bears South, 20.9 feet.

A 5/8" x 24" rebar with a yellow plastic cap marked "OR PLS 1106, WA PLS 17372", set in fence line, bears South, 43.5 feet.

Wired bearing object signs to rebar accessories. Wired witness sign to wire stay 1 1/2 feet South of corner monument.

LOCATION AND COMMENTS: Corner located in North-South fence line, between farmed fields.

**OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:**

N = 824814.35  
E = 8722649.11


FIRM: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East


Witness: Jason Wells, LSIT

/5N35L09

Surveyor's Seal



*William R. Wells*



Renews 6/30/06

05-112-c