

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 01/20/05

CORNER DESIGNATION: 5N35, N-25, The Northeast corner of Section 24.

PREVIOUS RENEWALS/SURVEYS ETC.:

Corner originally established by Odell & Lewis, under GLO Contract No. 110, dated February 7, 1865. Notes state: Set post Cor. for Secs. 13 & 24, 18 & 19, ravine, course N.W.; drove charred stake; dug pits & raised mound, as per instructions. Most recent survey, corner cert by Tomkins, 91-65-B.

The corner was recovered on Record of Private Surveys, Survey No. 5 and 16.

Loammasson found a stone at fence corner in 1976. In 1981, under Survey No. S-157-C, Krumbain found the stone and remonumented with a brass cap monument. The corner was recovered by Paul Tomkins in 1990 and reference accessories were added to the existing brass cap monument under corner record R-65-B. The brass cap corner monument has been used on all surveys requiring this corner since 1981.

MONUMENT AND ACCESSORIES FOUND:

Found 2 1/4" brass cap, Southwest of fence corner, with fences North-South and North 85° East, cap is marked as shown in Monument Marking Detail.

Existing accessories, from corner record R-65-B:

A 5/8" iron rebar with a yellow plastic cap stamped "TOMKINS" in fence bears North 00°13' West, 55.78 feet.

A 5/8" iron rebar with a yellow plastic cap stamped "TOMKINS" in fence bears North 85° 35' East, 57.36 feet.

A 5/8" iron rebar with a yellow plastic cap stamped "TOMKINS" in fence bears South 00° 23' East, 96.75 feet.

MONUMENT MARKING DETAIL:

T5N
R35E S13 | S18 R36E
S24 | S19
1981
PLS 933

New Accessories:

A 5/8" x 30" iron rebar with 1 1/4" yellow plastic cap stamped "OR PLS 1106, WA PLS 17372" flush with the ground at toe of field 1.5 feet East on fence bears North 02° East, 34.4 feet.

Attached bearing object sign to new rebar accessory. Nailed "witness" sign to fence corner post Northeast of corner monument.

LOCATION AND COMMENTS:

Corner is located Southwest of a fence corner with fences running North-South and North 85° East.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 822366.14
E = 8743763.07

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Witnesses: Jason Wells, LSIT
Brian Cole
/5N35N25

Surveyor's Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6/30/06

05-112-c