

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 03/10/05

CORNER DESIGNATION: 5N35, P-17, The East Quarter Corner of Section 22.

PREVIOUS RENEWALS/SURVEYS ETC.:

Corner was originally established by Odell & Lewis, under GLO Contract No. 110, dated February 7, 1865. Notes state: Set 1/4 Sec. post; drove charred stake; dug pits & raised mound, as per instructions.

J. W. Kimbrell recovered the original corner in his Record of Private Surveys, Survey No. 124, in 1900 and set a 22 x 9 x 7" stone and noted nearby stone accessories to the corner stone.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T5N R35E
1/4
S22 | S23
2005
PLS 1106

MONUMENT SET:

Corner falls in wheat field with no nearby features. I recovered certain features from J.W. Kimbrell's 1900 Survey No. 124, and held these features to re-establish this corner position, as described in "Detail" on Sheet 2 of 2 of the accompanying Record of Survey. At the re-established corner position, set a 5/8" x 24" rebar with a 2" aluminum cap, with cap buried 16" below ground level marked as shown in Monument Marking Detail.

New accessories:

- A silver deep-1 magnet buried 20" in the ground bears North 37° East, 28.2 feet.
- A purple deep-1 magnet buried 20" in the ground bears South 55° East, 28.4 feet.
- A blue deep-1 magnet buried 20" in the ground bears South 34° West, 27.4 feet.
- An orange deep-1 magnet buried 20" in the ground bears North 50° West, 26.1 feet.

Buried bearing object signs with all deep-1 magnets.

LOCATION AND COMMENTS: Corner is in a farmed field. There are no nearby features. One foot below ground at corner position is a very rocky ground in which a monument would not be deep enough to avoid being farmed out. Therefore a rebar driven into the rock was set.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 819800.30
E = 8733498.93


FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East


Surveyor's Seal

Witnesses: Jason Wells, LSIT
Brian Cole

/5N35P17



William R. Wells



Renews 6/30/06