

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 02/08/05

CORNER DESIGNATION: 5N35, R-23, The South Quarter Corner of Section 24.

PREVIOUS RENEWALS/SURVEYS ETC.:

Corner originally established by Odell & Lewis, under GLO Contract No. 110, dated February 7, 1865. Notes state: Set 1/4 Sec.; drove charred stake; dug pits; raised mound, as per instructions.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T5N R35E
1 S24
4 S25
2005
PLS 1106

MONUMENT SET:

I held the intersection of the center line of North-South County road with a old field berm, running West, as the best remaining evidence of the original corner location. At re-established corner point, set a 2 1/2" brass cap on a 1 1/2" x 30" galvanized iron pipe with cap buried 10" below road surface, and marked as shown in Monument Marking Detail.

New accessories:

A silver deep-1 magnet, buried 2.5 feet, in road bank, bears North 27° East, 26.2 feet.

A 5/8" x 30" rebar with yellow plastic cap marked "OR PLS 1106, WA PLS 17372", bears South 35° East 24.0 feet, set in road bank.

A 5/8" x 30" rebar with yellow plastic cap marked "OR PLS 1106, WA PLS 17372", bears South 40° West, 22.4 feet, set in road bank.

An orange deep-1 magnet, buried 2.0 feet, bears North 61° West, 25.7 feet.

Buried bearing object signs with deep-1 magnets. Wired bearing object signs to rebar accessories.

LOCATION AND COMMENTS: Corner located at intersection center line of North-South County Road and an old field berm West.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 817275.41
E = 8741675.76

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Witnesses: Jason Wells, LSIT
Brian Cole
/5N35R23

Surveyor's Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells
OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 6/30/06