

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 03/08/05

CORNER DESIGNATION: 5N35, T-17, The East Quarter Corner of Section 27.

PREVIOUS RENEWALS/SURVEYS ETC.:

Corner originally established by Odell & Lewis, under GLO Contract No. 110, dated February 7, 1865. Notes state: Set 1/4 Sec. post; drove charred stake; dug pits; raised mound, as per instructions.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T5N R35E
1/4
S27|S26
2005
PLS 1106

MONUMENT SET:

I re-established the corner position perpendicular to the midpoint of a line between the Southeast and Northeast corners of Section 27, and held existing North-South field berm for departure. At the re-established corner position, set 2 1/2" brass cap on a 2 1/2" by 30" galvanized iron pipe with cap 20" below ground level, marked as shown in Monument Marking Detail.

New accessories:

- A silver deep-1 magnet, buried 20" in ground, bears North 45° East, 35.1 feet.
 - A purple deep-1 magnet, buried 20" in ground, bears South 50° East, 35.8 feet.
 - A blue deep-1 magnet, buried 20" in ground, bears South 44 1/2° West, 34.4 feet.
 - An orange deep-1 magnet, buried 20" in ground, bears North 50 1/2° West, 36.4 feet.
- Buried bearing object signs with deep-1 magnets.

LOCATION AND COMMENTS: Corner is located in a North-South field line. No other nearby features.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 814475.20
E = 8733745.64

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT
Brian Cole

/5N35T17

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 6/30/06

05-112-c