

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 03/01/05

CORNER DESIGNATION: 5N35, T-09, The East Quarter Corner of Section 29.

**PREVIOUS RENEWALS/SURVEYS ETC.:**

Corner originally established by Odell & Lewis, under GLO Contract No. 110, dated February 7, 1865. Notes state: Set 1/4 Sec. post; drove charred stake; dug pits & raised mound, as per instructions.

In Record of Private Surveys, Survey No. 106 states: the 1/4 Sec. corner between Sec. 28 & 29 was recovered and noted at a point with fences North, West and South. Survey No. 182 reports identical measurements.

**MONUMENT AND ACCESSORIES FOUND:** Intersection of a East-West fence line and well defined field berm running South.

**MONUMENT MARKING DETAIL:**

T5N R35E  
1/4  
S29 | S28  
2005  
PLS 1106

**MONUMENT SET:**

I held the intersection of a East-West fence line with a well defined field berm running South as best remaining evidence of the original corner position. At re-established corner position, set a 2 1/2" brass cap on a 2 1/2" x 30" iron pipe, 28" in the ground. Cap marked as shown on Monument Marking Detail.

**New accessories:**

A 5/8" x 30" iron rebar with a 1 1/4" yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", with the cap 1" above ground level, in East-West fence line, bears East, 36.9 feet.  
A purple deep-1 magnet, buried 20" in the ground, bears South 25° East, 48.8 feet.  
A blue deep-1 magnet, buried 20" in the ground, bears South 54° West, 61.8 feet.  
A 5/8" x 30" iron rebar with a 1 1/4" yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", with the cap 1" above ground level, bears West, 42.8 feet.  
Buried bearing object signs with deep-1 magnets. Attached bearing object signs to rebar accessories. Attached "witness post" to railroad tie 8 feet West of brass cap monument.

**LOCATION AND COMMENTS:** Located in a East-West fence with a field berm running South.

**OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:**

N = 814325.78  
E = 8722792.74


**FIRM:** William R. Wells, PLS  
P.O. Box 1696  
Pendleton, OR 97801

**COMPASS DECLINATION:** 18° East

Surveyor's Seal

**Witnesses:** Jason Wells, LSIT  
Brian Cole

/5N35T09



Renews 6/30/06

05-112-C